

Addendum 1- to HVAC bid for the Georgetown High school

Addendum Issued April 8, 2015

Please be advised there are two changes to the bid document issued by the Georgetown school department.

1. Change 1 is the replacement of 31 exterior units and 33 interior units Mitsubishi or equivalent. Two of the Units are split units 1 roof top unit and 2 interior units. A list of units is below.
2. Change 2 is the Georgetown school department will be handling the disconnection of all outside units, Remove and recover existing R22 refrigerant, remove all the old outdoor units off the roof and dispose of them.

<u>Room #</u>	<u>Outside Unit Model#</u>	<u>Inside unit Model#</u>
3050	MUH12EN	MSH12EN wall mount
3040	MUH12EN	MSH12EN wall mount
2020	PU36EK	PC36EK recessed ceiling
2060	PU24EK	PC24EK recessed ceiling
2070	PU24EK	PC24EK recessed ceiling
1291	PUH24EK	PCH24EK recessed ceiling
1110	PUH24EK	PCH24EK recessed ceiling
1290	PUH30EK	PCH30EK recessed ceiling
3020	MUH12EN	MSH12EN wall mount
3030	PUH30EK	PCH30EK recessed ceiling
Library HP7	PUH24EK	PCH24EK recessed ceiling
Library HP6	PUH24EK	PCH24EK recessed ceiling

2164	PUL12EK	PLL12EK ceiling
2163	PUL12EK	PLL12EK ceiling
3120	PUH30EK	PCH30EK recessed ceiling
3140	PUH30EK	PCH30EK recessed ceiling
Library HP9	PUH24EK	PCH24EK recessed ceiling
1450	PUH24EK	PCH24EK recessed ceiling
Library HP8	PUH24EK	PCH24EK recessed ceiling
3160	PUH30EK	PCH30EK recessed ceiling
1152	PUH24EK	PCH24EK recessed ceiling
1240	PUH24EK	PCH24EK recessed ceiling
2162	PU24EK	PC24EK recessed ceiling
2161	PU24EK	PC24EK recessed ceiling
Main Office	PUH30EK	PCH30EK recessed ceiling
1014	MUH12EN	MSH12EN wall
1011 & 1012	MUM18EW	MS09EW(x2) walls
***(note for 1011 and 1012 the interior units are on abutting walls)		
1020 UNIT 1	MUH12EN	MSH12EN wall
1020 UNIT 2	MUH12EN	MSH12EN wall
1032 & 1031	MUM18EW	MS09EW(x2) walls
***(note for 1032 and 1031 the interior units are on abutting walls)		
1030	MUH12EN	MSH12EN wall